



TO ALL HOLDERS OF CONTRACT DOCUMENTS FOR:

**City of Las Vegas
Detention Center Lift Station Rehabilitation Project**

ADDENDUM NUMBER THREE

October 26, 2020

This Addendum shall be incorporated into the Contract Documents for the above referenced project.

Item No. 1 – Acceptable Coating Substitution

Based on initial review, the following coating system is acceptable as a substitution for the interior coatings of the lift station. All other requirements set forth in the technical specification shall still apply.

1. Apply Sherwin-Williams Dura-Plate 2300 Surfacer, applied by trowel or putty knife to fille large holes and bug holes, as necessary.
2. Prime Coat: Apply one coat of Zebron LT Primer at 1-3 mils DFT
3. Finish Coats: Apply Zebron 386 to 125 mils DFT

Item No. 2 – Existing Coatings

The Detention Center Lift Station does appear to have an existing tar epoxy coating. The existing coating will need to be mechanically removed completely (i.e. blast cleaning) during surface preparation.

All provisions of the contract documents not in conflict with Addendum No. 3 shall remain in full force. Receipt of this Addendum shall be acknowledged on the Bid Form.

Keaton Chancellor, PE
Souder, Miller & Associates

10/26/2020
Date